Working hours estimation and optimum amount of workers

| Model | Installing (measured in hours, h): structure + osb + roofing + insulating + exterior finishes + doors, windows | Optimum amount of workers |
|------------|--|---------------------------|
| Solo Hobby | 130160 | 2 |
| Solo 57 | 170210 | 2 |
| Solo 75 | 225275 | 2 |
| Solo 100 | 300360 | 2 |
| Duo 57 | 300360 | 2 |
| Duo 75 | 400480 | 2 |
| Duo 100 | 520640 | 2 |
| Duo 120 | 630770 | 2 |
| Trio 57 | 630770 | 24 |
| Trio 75 | 8551045 | 24 |
| Trio 100 | 11251375 | 24 |
| Trio 120 | 13501650 | 24 |
| Trio 150 | 17002100 | 24 |

| Average installation time for the optional extras | | |
|---|-------------|--|
| Erecting dormer | 16h | |
| Installing skylight | 4h | |
| Interior cladding installation | 1m2 = 0,45h | |

Notes

Keep in mind that those working hours are just estimates. The real hours depend on the workers speed and their skills.

This working hours estimation doesn't include the time to do the plumbing, wiring, HVAC, bathroom finishes, kitchen etc.

Get accurate working hours estimation from your local builder. Avrame is not responsible if the displayed working hours aren't the same as the local builder suggests.

Full budget calculation

Our self building guides provide you a lot of guidance when calculating out the full budget of the house. Get your copy <u>over</u> <u>here</u>. The more you plan your project ahead, the less chances there are to go over budget.

